
Reference	Fill Material Location	Material Description	AASHTO Designation	Compaction Requirements
④	Final backfill / material to grade	For backfill, the design engineer will specify suitable native or engineered materials to create a stable subgrade as outlined in the project plans. Recommended material should be at minimum 12" of clean, well-graded soil.	Not applicable (N/A)	Subgrade preparation will follow strict specifications on the site plans, which may include additional requirements for paved installations as determined by the site engineer. The degree of soil compaction should correspond with existing soil and water conditions and future external load.
③	Initial backfill / cover over system	Granular well-graded soil/aggregate mixtures, < 35% fines, most pavement subbase materials can be used in this layer.	AASHTO M145 A-1, A-2-4, A-3 AASHTO M43 3, 357, 4, 467, 5, 56, 57, 6, 67, 68, 7, 78, 8, 9, 10	Compaction begins after 12" of material placement over the system, with subsequent lifts no greater than 12" for well-graded materials of 6" for processed aggregates, all compacted to a minimum of 95% standard Proctor density (SP)
②	Embedment / perimeter material	Clean, crushed angular stone; Native soil or sand compacted per application requirements.	AASHTO M43 3, 357, 4, 467, 5, 56, 57	
①	Foundation / bedding material			Bedding must be uniform, level and free of debris, at a minimum depth of 4" and compacted to a minimum density of at least 95% standard Proctor density (SP), or as required by engineer.



Notes:

A. Reference **Installation Min. Loading & Depth Requirements (AQ-100-02)** for load, compaction, and min/max depth requirements.
B. Reference **Geosynthetics Detail (AQ-100-03)** for minimum fabric material weights and application details.
C. Reference **AquaCell Installation Guide** for further information and instruction on installation of backfill material.

***Sub-base must provide a minimum bearing capacity of 2,000 lbs/ft² prior to installing foundation materials and/or AquaCell system**


Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us
wavintechsupport@orbia.com


The design details/specifications presented in this document are for informational purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests soley with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com

Title: AquaCell Acceptable Backfill Materials Table
Date: 10/28/2025 | Scale: NTS | Drawing: AQ-100-01 | Rev: 4
Drawn: HJD | Approved: JS | Sheet: 1 of 1

Load Rating Ⓐ	Min. / Max. Top Cover (SC) Ⓑ	Min. / Max. Top Cover (EX) Ⓒ	Soil Compaction (SP) Minimum Ⓓ	Compacted Backfill Lifts Min. / Max. Ⓔ
Light Duty < 2,500 lbs	12 inches / 14.4 feet	12 inches / 26.2 feet	90% SP (Standard Proctor)	6 in. /12 in.
H-10 Traffic Loading	12 inches / 14.4 feet	12 inches / 26.2 feet	95% SP (Standard Proctor)	6 in. /12 in.
HS-20 Traffic Loading	18 inches [1] / 14.4 feet	16 inches [2] / 26.2 feet	95% SP (Standard Proctor)	6 in. /12 in.
HS-25 Traffic Loading	30 inches / 14.1 feet	22 inches / 26.1 feet	98% SP (Standard Proctor)	6 in. /12 in.

Additional Notes	[1]18 inches based on 10" x 10" contact area	[2]16 inches based on 9" x 9" contact area	Each project must conduct a stress analysis to ensure the system's stability based on the actual loads, soil type and water table involved. Wavin recommends a minimum cover of 12 inches over the top of the tank. For details on use in the standard (SC) or extra strong (EX) versions, or if you need further information, contact your local Wavin representative directly.






Notes:

A. **AASHTO** ratings follow standard classification of truck axle loading weights for live loads.
B. Reference **AquaCell Cover Depths by Configuration (AQ-100-08.2)** and **AquaCell Installation Guide** for further information and instructions related to installation depths.
C. **AquaCell Extra Strong (EX)** consists of two base units inset within each other. Reference **TB101 & TB102 Load Capacity Testing Results** for additional information.
D. On-site soil compaction minimum percentage of **Standard Proctor Density (SP)** per **ASTM D698** and **ASTM D1557** as applicable.
E. Reference **Construction Loads over AquaCell System (AQ-100-20)** and **AquaCell Installation Guide** for guidelines on compaction and machinery used during installation.
F. The minimum width of sidewall backfill is **12 inches** or large enough to accommodate selected compaction equipment, whichever is greater.
G. Reference **Backfill Materials Table (AQ-100-01)** for recommended materials, AASHTO designations.

Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us
wavintechsupport@orbia.com

The design details/specifications presented in this document are for informational purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests soley with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com

Title: AquaCell Installation Minimum Loading Requirements
Date: 4/1/2026 | Scale: NTS | Drawing: AQ-100-02 | Rev: 5
Drawn: HJD | Approved: JS | Sheet: 1 of 1




Notes:

A. For **Retention/ Infiltration systems**, provide a geotextile fabric with a minimum permittivity of 1.4 sec^-1. This will provide rapid water flow through the fabric which is essential to maintain infiltration performance and reduce the risk of clogging over time.
B. Wrapping the **AquaCell** system with geotextile also provides protection against abrasion, puncture, and UV degradation before and during installation. **Geosynthetics provided by others**.
C. Geotextile is layered around entirety of stone backfill & completely wrapped after initial backfill/ cover over top of tank is complete. Final backfill installed to surface grade as designed by E.O.R.
D. Reference **AquaCell Installation Guide** for further information and instruction on geosynthetics installation.

Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us
wavintechsupport@orbia.com

The design details/specifications presented in this document are for informational purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests soley with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com

Title: AquaCell Infiltration Detail
Date: 12/1/2025 | Scale: NTS | Drawing: AQ-100-03.1 | Rev: 3
Drawn: HJD | Approved: JS | Sheet: 1 of 1



Notes:


A. For **Detention & Reuse systems**, provide a *WT liner (minimum 30 mil geomembrane) with a thickness tolerance of ± 5% as defined by ASTM 5199.
B. The **AquaCell tank** shall be wrapped with a min. 6 oz./ yd² non-woven geotextile fabric. An impermeable liner is **not required** directly around the AquaCell unless specified by the E.O.R.
B.1. Choose geomembrane fabric based on site specific applications. Material should be puncture resistant and durable. **Geosynthetics provided by others**.
C. It is recommended that the geomembrane is protected with an inner & outer layer of min. 6 oz./yd² non-woven geotextile to protect the WT liner from puncture or damage during installation.
D. Reference **AquaCell Installation Guide** for further information and instruction on geosynthetics installation.
E. Woven geotextiles may also be used as a protective layer wrapping the geomembrane to provide abrasion and puncture resistance during installation, as approved by E.O.R.

Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us
wavintechsupport@orbia.com

The design details/specifications presented in this document are for informational purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests soley with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com

Title: AquaCell Detention Detail
Date: 4/14/2026 | Scale: NTS | Drawing: AQ-100-03.4 | Rev: 4
Drawn: HJD | Approved: JS | Sheet: 1 of 1

Project Name	Project #	Revision #	Date	Tank Model	Contact Info	Wavin.us
			Nov. 2026			



Notes:


12" | 16" Top Adapter (3085857 | 2476842000) available for installation of a vertical pipe for venting and/or inspection into **AquaCell** tank. All castings provided by **OTHERS**.

1. Install vertical **12" PVC SDR-35/26 GASKETED bell end pipe (ASTM D3034/ F477)** over riser of 12" Top Adapter (Traffic | Non-traffic).
2. Install vertical **12" PVC SDR-35/26 PLAIN end pipe (ASTM D3034)** over riser of 12" Top Adapter (Traffic | Non-traffic). Use 12" flexible coupler & stainless steel straps to secure pipe & adapter.
3. Install vertical **12" HDPE plain end pipe (ASTM F2306 | F2648)** in riser of 16" top adapter **(Non-traffic applications only)**. Wrap fabric around 12" Top Adapter and wrap with corrosion-resistant tape
4. **Not Shown** - **18" SCH.40 plain end pipe w/ ID 16.81" (ASTM D2665)** over riser of **16" Top Adapter** (Traffic | Non-traffic).
5. Reference **AquaCell Installation Guide** & **AquaCell Compatible Pipe Connections (AQ-200-0**2) for further information and instruction on vertical & lateral pipe connections.

Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us
wavintechsupport@orbia.com

The design details/specifications presented in this document are for informational purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests soley with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com

Title: AquaCell Top Adapter Connection Detail			
Date: 6/24/2025	Scale: NTS	Drawing: AQ-100-04	Rev: 3
Drawn: HJD	Approved: JS	Sheet: 1 of 1	




Notes

1. **AquaCell Side Plate (2476600003)** contains two integrated 6" pipe inlets (6.4" OD) with stoppers. Use 6" PVC SDR-26/35 (ASTM D3034) for connection to **AquaCell** tank[5].
2. **AquaCell 8-12" Pipe Connector (2476631200)**
   2.1. To connect 8" pipe to **8-12" Pipe Connector** spigot (7.9" OD), use PVC SDR-26/35, SCH. 40, or HDPE pipe. Additional coupler / pipe solvent may be needed (provided by others).
3. To connect 12" pipe to the 12" spigot (12.4" OD) connection on **8-12" Pipe Connector**:
   3.1. Existing 8" eccentric spigot end on adapter should be cut and removed entirely, creating a 12" spigot end ready to connect 12" pipe to the **AquaCell Side Plate**.
   3.2. Use gasketed bell end of 12" PVC SDR/26-35 pipe or adapter and install directly over the 12" spigot (provided by others).
   3.3. For 12" connections having dissimilar material, use a 12.5" flexible rubber coupler or corrosion-resistant mastic tape to weld pipe to **8-12" Pipe Connector** (provided by others).
4. Reference **AQ-200-02 AquaCell Compatible Pipe Connections** detail for information regarding compatible pipe types to **8-12" Pipe Connector**.
5. Reference **AQ-100-22 Six-inch PVC Pipe to AquaCell Side Panel Detail** (Note 1)
6. Reference **AquaCell Installation Brochure** for further information regarding pipe connections to **AquaCell** system.

Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us
wavintechsupport@orbia.com

The design details/specifications presented in this document are for informational purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests soley with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com

Title: **AquaCell Connections by Pipe Type**			
Date: **8/5/2025**	Scale: **NTS**		Rev: **2**
Drawn: **HJD**	Approved: **JS**	Drawing: **AQ-100-07**	




Notes:

1. For pipe connections to **AquaCell** ≥ 16 inches, connect to **Side Plate (2476600003)** using a HDPE/PP stub out adapter (***optional***) with geotextile "boot" wrapped around the pipe.
   1.1. If using a custom pipe adapter, secure to the **AquaCell Side Plate** ***before*** wrapping the tank with geotextile.
2. *Cut hole or sections in Side Plate ± diameter of inlet pipe ID to allow for open area with no obstruction for water flow.*
3. Cut an "X" in the geotextile fabric wrapped directly around the tank slightly larger than the pipe pipe OD.
4. Pull the fabric opening around the pipe, then slide pipe against the AquaCell side panels (or pull fabric around the stub out previously installed).
5. Weld the boot sleeve to the pipe using corrosion resistant adhesive tape (duct tape).
6. Secure the connection around the pipe & geotextile with stainless steel hose clamps (recommended min. two (2) for connections ≥ than 24 inches).
7. All custom adapters ≥ 16 inches, adhesive tape, hose clamps, and geotextile ***provided by others***.
8. Reference **AquaCell Installation Guide** for additional information/ guidance when installing pipe boot.

Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us
wavintechsupport@orbia.com

The design details/specifications presented in this document are for informational purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests soley with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com

Title: AquaCell Large Diameter Pipe Abutment (Geotextile Boot)			
Date: 8/25/2025	Scale: NTS	Sheet: 1 of 1	Rev: 2
Drawn: HJD	Approved:	Drawing: AQ-100-10	



Notes:

Fill Placement and Initial Compaction

a. Recommended fill placement method is by tracked excavator operating from outside the AquaCell footprint.
a.a. No compaction equipment shall operate directly on exposed AquaCell units until minimum cover is achieved.
b. Backfill the first 12" layer with an excavator placed outside the footprint and compact with a roller which has an operating weight not exceeding 6 US tons.
c. A minimum of 24" compacted cover measured from the top of the AquaCell units shall be in place before operating a vibratory roller.

Backfill Compaction Standards

d. Backfill should be compacted as required with no loose fill.
d.a. Recommended soil compaction: 90% Standard Proctor for light duty < 2,500 lbs., 95% Standard Proctor for H-10 & HS-20, and 98% Standard Proctor for HS-25 traffic loading.

Construction vs. Final Design Loading

e. The construction loading limits shown apply only during installation, prior to completion of the pavement section.
e.a. These limits should not be interpreted as the final design traffic capacity of the AquaCell system.
e.b. Equipment exceeding the published construction loading limits shall be reviewed by Wavin Technical Support or the engineer of record.
e.c. Final design traffic loads (e.g., HS-20, HS-25) are evaluated based on the completed pavement structure and are significantly greater than construction loading limits.
f. Construction loading conditions and final traffic design loading conditions are not equivalent.
f.a. The final traffic capacity of the AquaCell system is achieved only after the required compacted cover and pavement structure are fully installed.

Proof Rolling and Project Specific Conditions


g. Proof rolling requirements may vary by project.
g.a. Equipment selection and minimum cover requirements should be reviewed based on the project specifications and anticipated construction loads.
g.b. Proof rolling operations conducted with adequate compacted cover (typically ≥ 24" to 36") may be performed using standard geotechnical proof-rolling equipment.
g.c. Consult the engineer of record or Wavin Technical Support if conditions differ.

Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us
wavintechsupport@orbia.com

The design details/specifications presented in this document are for informational purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests soley with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com

Title: Construction Loads Over AquaCell System			
Drawn: HJD	Scale: n.t.s.	Drawing #: AQ-100-20	Rev: **2**
Approved: JS		Date: 9/25/2026	

Project Name	Project #	Revision #	Date	Tank Model	Contact Info	Wavin.us
			Nov. 2026			



NOTES:

1. Filtration bags (provided by others) are recommended for any grated inlet (provided by others) into the **AquaCell** to prevent sediment & debris from entering the system.
2. Below grade, under grate sediment bags are recommended for both traffic and non-traffic applications.
   a) Remove the grate from the casting. Clean debris around the frame.
   b) Place the filter bag onto the frame of the casting following manufacturer's installation details.
   c) Replace the grate into the casting and secure.
3. The size of the sediment filter bag will depend on the size of the grated inlet casting and as specified by the design engineer.
4. For stormwater applications, a sediment filter bag with a micron rating of 100 to 200 microns is typically sufficient or as specified by the design engineer.
5. Recommended filtration bags of non-woven geotextile fabric or polypropylene should be used or as specified by design engineer.

Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us.com
wavintechsupport@orbia.com

Title: Sediment Bag Installation from a Grated Inlet into AquaCell


The design details/specifications presented in this document are for informational & reference purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests solely with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com.


Drawn by: HJD	Approved by: KS
Scale: NTS	Revision: 0
AQ-100-19	Date: 7/18/2024

Sheet _1_of_1_

WAVIN PT-ROW™ (Pre-Treatment Row)

1. **FABRIC PLACEMENT:** WOVEN MONOFILAMENT PP GEOTEXTILE FABRIC LAID ABOVE BASE LAYER OF NON-WOVEN GEOTEXTILE AND BELOW THE BOTTOM PLATES OF THE DESIGNATED **PT-ROW™** AREA.
   1.1. EXTEND WOVEN FABRIC OUTWARD TO THE LENGTH AND WIDTH OF THE DESIGNED AREA (SINGLE OR MULTI-STACK).
   1.2. ENSURE ENOUGH FABRIC IS EXTENDED BEYOND THE **PT-ROW™** AREA TO WRAP SIDE FABRIC TO THE TOP/ UPPER DECK OF CRATES. (18" FOR SINGLE LAYER, 36" FOR DOUBLE LAYER, 48" FOR TRIPLE LAYER).
2. INSTALL BASE UNITS TO THE BOTTOM PLATES TO CREATE THE ROW / CHANNEL TO BE WRAPPED WITH WOVEN FABRIC.
3. ONCE **PT-ROW™** CHANNEL IS BUILT, BRING WOVEN FABRIC LOCATED BELOW THE BOTTOM PLATES UP AND AROUND SIDES OF THE CRATE ROW.
   3.1. TO SECURE THE WOVEN FABRIC TO THE **PT-ROW™**, FIND THE INTEGRATED SIDE PLATE SLOTS ON THE TOP DECK AND CUT THE FABRIC TO ENSURE A CLEAR OPENING TO INSTALL THE SIDE PLATE.
   3.2. INSTALL THE SIDE PLATE BY SECURING THE HINGES IN THE TOP DECK AND LOWERING THE SIDE PLATE TO CONNECT TO THE BOTTOM PLATE CONNECTORS.
   3.3. THE WOVEN FABRIC WILL BE SECURED BEHIND THE SIDE PLATES ALONG THE LENGTH OF THE DESIGNATED **PT-ROW™**.
4. FOR DOUBLE & TRIPLE MULTI-STACK **PT-ROW™**, EXTEND AND CONNECT THE WOVEN FABRIC TO THE UPPERMOST TOP DECK AND SECURE THE FABRIC PER NOTE 3.
5. AT THE BACK END OF THE **PT-ROW™**, PULL OVERLAP UP TO UPPER DECK AND SECURE PER NOTE 3.
6. INSPECTION / MAINTENANCE CLEANOUTS TO BE LOCATED ABOVE **PT-ROW™** LOCATIONS.
   6.1. CLEANOUTS RECOMMENDED EVERY 50' TO 100' (MINIMUM ONE AT BEGINNING OF EACH **PT-ROW™**).
7. **PT-ROW™** DETAILS SHOWN FOR EXAMPLE ONLY. EXACT DIMENSIONS OF **PT-ROW™** TO BE DETERMINED BY E.O.R.
   7.1. REFERENCE **WAVIN AQUACELL PT-ROW™ SIZING AND DESIGN GUIDANCE** DOCUMENT FOR ADDITIONAL INFORMATION.
   7.2. REFERENCE **AQUACELL INSTALLATION GUIDE** AND **AQUACELL O&M MANUAL** FOR INFORMATION ON CLEANING & MAINTENANCE OF **PT-ROW™**.





Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us
wavintechsupport@orbia.com

The design details/specifications presented in this document are for informational purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests soley with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com


Title: **AquaCell PT-ROW™ INSTALLATION GUIDANCE**


Date: **9/5/2025**	Scale: **NTS**		Rev: **3**
Drawn: **HJD**	Approved:	Drawing: **AQ-100-25**	

AquaCell Crate With Bottom Plate *(1st Layer Only)*	# Layers	Height of Layers (ft)	Height of Layers (in)	Water Volume (ft^3)	Total Crate Volume (ft^3)	Percentage Water
SC-1	1	1.39	16.73	10.25	10.81	94.87%
SC-2	2	2.71	32.48	20.0	20.98	95.33%
SC-3	3	4.02	48.23	29.7	31.15	95.49%
SC-4	4	5.33	63.98	39.5	41.32	95.57%
SC-5	5	6.64	79.72	49.2	51.49	95.62%
SC-6	6	7.96	95.47	59.0	61.66	95.65%
SC-7	7	9.27	111.22	68.7	71.83	95.67%
SC-8	8	10.58	126.97	78.5	82.00	95.69%

AquaCell Crate + Bottom +1 Side Plate	# Layers	Height of Layers (ft)	Height of Layers (in)	Water Volume (ft^3)	Gross Volume total (ft^3)	Percentage Water
SC-1	1	1.39	16.73	10.17	10.81	94.13%
SC-2	2	2.71	32.48	19.84	20.98	94.57%
SC-3	3	4.02	48.23	29.50	31.15	94.72%
SC-4	4	5.33	63.98	39.17	41.32	94.79%
SC-5	5	6.64	79.72	48.83	51.49	94.84%
SC-6	6	7.96	95.47	58.50	61.66	94.87%
SC-7	7	9.27	111.22	68.16	71.83	94.90%
SC-8	8	10.58	126.97	77.83	82.00	94.91%

AquaCell Crate + Bottom + 2 Side Plates	# Layers	Height of Layers (ft)	Height of Layers (in)	Water Volume (ft^3)	Gross Volume total (ft^3)	Percentage Water
SC-1	1	1.39	16.73	10.09	10.81	93.39%
SC-2	2	2.71	32.48	19.68	20.98	93.80%
SC-3	3	4.02	48.23	29.26	31.15	93.95%
SC-4	4	5.33	63.98	38.85	41.32	94.02%
SC-5	5	6.64	79.72	48.43	51.49	94.07%
SC-6	6	7.96	95.47	58.02	61.66	94.10%
SC-7	7	9.27	111.22	67.60	71.83	94.12%
SC-8	8	10.58	126.97	77.19	82.00	94.13%





Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us.com
wavintechsupport@orbia.com

Title: AquaCell Volume Calculations - Standard (SC) Configuration

The design details/specifications presented in this document are for informational & reference purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests solely with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com.


Drawn by: HJD	Approved by: KS
Scale: NTS	Revision: 4
AQ-200-01	Date: 11/10/25


Sheet _1_of_2_

AquaCell Crate + (2 Base Units)	# Layers	Height of layers (ft)	Height of Layers (in)	Water Volume (ft^3)	Total Crate Volume (ft^3)	Percentage water
EX-1	1	1.51	18.11	10.83	11.70	92.63%
EX-2	2	3.02	36.22	22.11	23.39	94.50%
EX-3	3	4.53	54.33	33.38	35.09	95.12%
EX-4	4	6.04	72.44	44.65	46.78	95.43%
EX-5	5	7.55	90.55	55.92	58.48	95.62%
EX-6	6	9.06	108.66	67.19	70.18	95.74%
EX-7	7	10.56	126.77	78.46	81.87	95.83%
EX-8	8	12.07	144.88	89.73	93.57	95.90%

AquaCell Crates + 1 Side Plate	# Layers	Height of layers (ft)	Height of Layers (in)	Net Volume water (ft^3)	Gross Volume total (ft^3)	Percentage water
EX-1	1	1.51	18.11	10.75	11.70	91.95%
EX-2	2	3.02	36.22	21.95	23.39	93.81%
EX-3	3	4.53	54.33	33.14	35.09	94.44%
EX-4	4	6.04	72.44	44.33	46.78	94.75%
EX-5	5	7.55	90.55	55.52	58.48	94.93%
EX-6	6	9.06	108.66	66.71	70.18	95.06%
EX-7	7	10.56	126.77	77.90	81.87	95.15%
EX-8	8	12.07	144.88	89.09	93.57	95.21%

AquaCell Crates + 2 Side Plate	# Layers	Height of layers (ft)	Height of Layers (in)	Net Volume water (ft^3)	Gross Volume total (ft^3)	Percentage water
EX-1	1	1.51	18.11	10.67	11.70	91.27%
EX-2	2	3.02	36.22	21.79	23.39	93.13%
EX-3	3	4.53	54.33	32.90	35.09	93.75%
EX-4	4	6.04	72.44	44.01	46.78	94.06%
EX-5	5	7.55	90.55	55.12	58.48	94.25%
EX-6	6	9.06	108.66	66.23	70.18	94.38%
EX-7	7	10.56	126.77	77.34	81.87	94.46%
EX-8	8	12.07	144.88	88.45	93.57	94.53%





Managing water better since 1955.
950 Winter Street
Waltham, MA 02451
wavin.us.com
wavintechsupport@orbia.com

Title: AquaCell Volume Calculations - Extra Strong (EX) Configuration

The design details/specifications presented in this document are for informational & reference purposes only and are subject to change without notice. Responsibility for design of any AquaCell system rests solely with the original design engineer of record. For questions, contact: wavintechsupport@orbia.com.

Drawn by: HJD	Approved by: KS
Scale: NTS	Revision: 4
AQ-200-01	Date: 11/10/25

Sheet _2_of_2_

Project Name	Project #	Revision #	Date	Tank Model	Contact Info	Wavin.us
			Nov. 2026			